


COUNTY ROAD TRENCH RESTORATION

NOTES:


1. 6" STABILIZED BASE IS TO BE BROUGHT TO THE TOP OF EXISTING PAVEMENT AT THE END OF EACH DAY AND LEFT IN PLACE FOR APPROXIMATELY 6 MONTHS.
2. AFTER SETTLEMENT, THE TRENCH WIDTH PLUS ONE FOOT ON BOTH SIDES ARE TO BE MILLED OUT 2" DEEP AS PER APPROPRIATE MILLING LIMITS ABOVE AND REPAVED USING BITUMINIOUS CONCRETE SURFACE COURSE MIX I-5.
3. EXISTING TRAFFIC STRIPES TO BE REPLACED FOLLOWING FINAL PAVEMENT.
4. ALL TRENCHES TO BE SAW CUT.



TOWNSHIP ROAD TRENCH RESTORATION

NOTES:

1. 4" STABILIZED BASE IS TO BE BROUGHT TO THE TOP OF EXISTING PAVEMENT AT THE END OF EACH DAY AND LEFT IN PLACE FOR APPROXIMATELY 6 MONTHS.
2. AFTER SETTLEMENT, THE TRENCH WIDTH PLUS ONE FOOT ON BOTH SIDES ARE TO BE MILLED OUT 1.5" DEEP AS PER APPROPRIATE MILLING LIMITS ABOVE AND REPAVED USING BITUMINIOUS CONCRETE SURFACE COURSE MIX I-5.
3. EXISTING TRAFFIC STRIPES TO BE REPLACED FOLLOWING FINAL PAVEMENT IF REQUIRED.
4. ALL TRENCHES TO BE SAW CUT.



GENERAL NOTES:

1. UNSUITABLE MATERIAL ENCOUNTERED BENEATH THE TRENCH TO BE REMOVED TO A DEPTH DETERMINED BY THE ENGINEER. REFER TO THE TECHNICAL SPECIFICATIONS FOR DETAILED PIPE BEDDING REQUIREMENTS.
2. SUITABLE BACKFILL TO BE THOROUGHLY COMPACTED IN 6" LIFTS BY MECHANICAL TAMPING (OR BY HAND TAMPING WHEN AND WHERE DIRECTED).
3. AREAS SURROUNDING PIPE SHALL BE HAND TAMPED TO FILL ALL CAVITIES.
4. THE CONTRACTOR MUST DEWATER PRIOR TO PLACING THE PIPE IF WET TRENCH CONDITIONS ARE FOUND. THE PIPE MUST REMAIN IN DRY CONDITIONS UNTIL BACKFILLED.



Title **TRENCH RESTORATION DETAIL**

**JACKSON TOWNSHIP
MUNICIPAL UTILITIES AUTHORITY**

135 Manhattan St., Jackson, NJ 08527 732-928-2222 www.jacksonmua.com

DRAWING No.	03		
	02	May 15, 2018	NEW TITLE BLOCK
	01	March 2010	
No.	Date	REVISION	
Date	FEB 2003	Scale	N.T.S.
Revised By			<i>JSD</i>