


1. ALL NEWLY INSTALLED TAPPING SLEEVES & TAPPING VALVES SHALL BE PNEUMATICALLY TESTED AT A TEST PRESSURE OF 150PSI FOR A PERIOD OF THIRTY MINUTES. AT THE END OF THE TEST PERIOD, IF THE TEST PRESSURE HAS REMAINED CONSTANT, THE TAPPING SLEEVE & VALVE SHALL HAVE PASSED THE TEST.
2. ANY VALVE (WATER OR FORCE MAIN) INSTALLED OUTSIDE OF ASPHALT AREAS MUST BE CONSTRUCTED WITH A 2'x2'x6" CONCRETE COLLAR AROUND IT.



<b>JACKSON TOWNSHIP MUNICIPAL UTILITIES AUTHORITY</b> 135 Manhattan St., Jackson, NJ 08527 732-928-2222 www.jacksonmua.com	Title	<b>WET TAP CONNECTION</b>		DRAWING No.	03	May 24, 2018	NEW TITLE BLOCK AND NOTES
					02	April 2011	
					01	March 2010	
		No.	Date	REVISION			
	Date	FEB 2003	Scale	N.T.S.	Revised By	JSD	